

PART 1 - GENERAL

1.1 DESCRIPTION

- A. Provide Air Cleaning Devices as specified herein and as shown on the Drawings.
- B. Materials characteristics and size shall be as indicated on the Drawings.
- C. Related Work: The requirements of Section 23 05 00, Common HVAC Materials and Methods, also apply to this section.

1.2 QUALITY ASSURANCE

- A. Air Equipment Rating: In accordance with ASHRAE 52.2-2007.

1.3 SUBMITTALS

- A. Submit catalog data, construction details and performance characteristics for all manufactured materials.
- B. Submit operating and maintenance data.

PART 2 - PRODUCTS

2.1 AIR FILTERS

- A. Disposable Media, MERV 8 Rated:
 - 1. Disposable, preformed 100% synthetic non-woven media, pleated 2" thick cartridge type with carrier board frames with diagonal and horizontal supports. Average ASHRAE test efficiency of MERV 8 per ASHRAE 52.2-2007 App J with initial pressure drop across the clean filter bank not exceeding 0.2" W.C. when operating at 500 FPM. The filter media shall have an Underwriters Laboratories UL 900 Class 2 listing.
 - 2. Provide specified filters for temporary heat and testing during construction and replace filters with new clean, specified filters prior to acceptance of project by Owner (two complete sets of media are required).
 - 3. Flanders or equal.

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION

- A. Air Handling Equipment Installation and Arrangement: Install and arrange as shown on Drawings. Comply with the manufacturer's recommendations for installation, connection, and start-up.
- B. Equipment Access Panels: Locate free of all obstructions such as ceiling bars, electrical conduit, lights, ductwork, etc.
- C. Filters: Install specified filters or accepted substitute temporary construction filters in supply units and systems prior to start-up or use for drying and/or temporary heat. Provide 2 sets of filters and replace prior to acceptance of project.
- D. Install and arrange equipment as shown on the Drawings and as recommended by the equipment manufacturer.

END OF SECTION