




1 BASEMENT KITCHEN ELECTRICAL PLAN
E3.2 SCALE: 1/4" = 1'-0"



2 HOOD SHUTDOWN CONTROL DIAGRAMS
E3.2 SCALE: NTS

NOTE 1. →
NOTE 1. →
NOTE 1. →

NOTE 1. →
NOTE 1. →
NOTE 1. →

NOTE 1. →

KITCHEN EQUIPMENT SCHEDULE								
NO.	EQUIPMENT NAME	HP/KW	VOLTS	PH	AMPS	CONDUIT	WIRE	CIRCUIT
4A	REACH-IN REFRIGERATOR	---	120	1	7.3 A	1/2"	2 #12	BNK1-39.
4B	REACH-IN REFRIGERATOR	---	120	1	7.3 A	1/2"	2 #12	BNK1-41.
5	REACH-IN FREEZER	---	120	1	11.0 A	1/2"	2 #12	BNK1-37.
15A	REACH-IN FREEZER	---	120	1	11.0 A	1/2"	2 #12	BNK1-13.
15B	REACH-IN FREEZER	---	120	1	11.0 A	1/2"	2 #12	BNK1-15.
26	DISHMACHINE W/ BOOSTER	---	208	3	42.1 A	1"	3 #6	BNK1-7,9,11.
28	WASTE COLLECTOR	---	120	1	11.0 A	1/2"	2 #12	BNK1-5.
40	PATIENT DELIVERY CART	---	120	1	13.7 A	1/2"	2 #12	BNK1-25.
41	REACH-IN REFRIGERATOR	---	120	1	4.8 A	1/2"	2 #12	BNK1-27.
42	TYPE 1 HOOD LIGHTS	---	120	1	1.0 A	1/2"	2 #12	BNK1-29.
44A	CONVECTION OVEN	---	120	1	6.0 A	1/2"	2 #12	BNK1-31.
44B	CONVECTION OVEN	---	120	1	6.0 A	1/2"	2 #12	BNK1-33.
55	5 QT. MIXER	---	120	1	3.0 A	1/2"	2 #12	BNK1-35.
60	REFRIGERATED PREP STATION	---	120	1	12.0 A	1/2"	2 #12	BNK1-43.
70	RANGE / CONVECTION OVEN	---	120	1	3.4 A	1/2"	2 #12	BNK1-62.
75	FRYER	---	120	1	6.1 A	1/2"	2 #12	BNK1-66.
78	CONVECTION STEAMER	---	208	3	23.6 A	1/2"	3 #10	BNK1-68,70,72.
82	MICROWAVE OVEN	---	120	1	13.4 A	1/2"	2 #12	BNK1-60.
84	REACH-IN	---	120	1	12.0 A	1/2"	2 #12	BNK1-58.
85	TYPE 1 HOOD LIGHTS	---	120	1	3.0 A	1/2"	2 #12	BNK1-64.
87	ICE TEA BREWER	---	120	1	13.8 A	1/2"	2 #12	BNK1-17.
90	HOT BEVERAGE DISPENSER	---	120	1	15.0 A	1/2"	2 #12	BNK1-19.
95	COFFEE MAKER	---	120/208	1	27.5 A	1/2"	3 #10	BNK1-21,23.
102A	PEDESTAL OUTLET	---	120	1	15.0 A	1/2"	2 #12	BNK1-67.
102B	PEDESTAL OUTLET	---	120	1	15.0 A	1/2"	2 #12	BNK1-69.
106	HOT FOOD TABLE	---	208	1	20.0 A	1/2"	2 #12	BNK1-63,65.
107	PLATE DISPENSER	---	120	1	9.0 A	1/2"	2 #12	BNK1-59.
108	LIGHTED SNEEZE GUARD	---	120	1	3.0 A	1/2"	2 #12	BNK1-61.
112	SOUP WARMER	---	208	1	6.0 A	1/2"	2 #12	BNK1-55,57.
114	DROP-IN CHILLED PAN	---	120	1	7.0 A	1/2"	2 #12	BNK1-53.
115	LIGHTED SNEEZE GUARD	---	120	1	3.0 A	1/2"	2 #12	BNK1-51.
117	SNEEZE GUARD	---	120	1	3.0 A	1/2"	2 #12	BNK1-49.
119	SELF-SERVICE CASE	---	120	1	14.0 A	1/2"	2 #12	BNK1-47.
125	ICE MAKER	---	120	1	20.0 A	1/2"	2 #12	BNK1-45.

KITCHEN SCHEDULE NOTES:

NOTE 1: ROUTE EQUIPMENT BRANCH CIRCUIT VIA CONTROL CONTACTOR. SEE 2 E3.2

KITCHEN GENERAL NOTES:


A. VERIFY ALL EQUIPMENT ELECTRICAL REQUIREMENTS PRIOR TO ROUGH-IN.

B. KITCHEN ELECTRICAL PLAN IS SHOWN FOR GENERAL REFERENCE ONLY. SEE KITCHEN DRAWINGS FOR SPECIFIC ROUGH-IN AND ELECTRICAL REQUIREMENTS.

PLAN NOTES

- ROUTE BRANCH CIRCUIT VIA CONTROL CONTACTOR. SEE 2 E3.2
- DIGITAL MENU BOARD. VERIFY LOCATION PRIOR TO ROUGH-IN.
- GAS SOLENOID VALVE. COORDINATE LOCATION WITH PLUMBING DRAWINGS.
- CONTROL SWITCH FOR HOOD FAN AND HOOD LIGHTS. SWITCHES LOCATED IN HOOD CONTROL PANEL. SEE KITCHEN DRAWINGS FOR CONTROL REQUIREMENTS.

Consulting Engineers
2007 S.E. Ash St.
Portland, OR 97214
PH: (503) 234-0548
FAX: (503) 234-0677
WWW.MFIA-ENG.COM
CONTACT: CHRIS WINER



BLUE ROOM ARCHITECTURE & DESIGN, P.S.

HISTORIC SALTESE SCHOOLHOUSE
BOX 628, VERADALE, WA 99037
(509) 456-6800

www.brdstudio.com

CIVIL ENGINEER

FOOD SERVICE CONSULTANT
DK DESIGN, INC.
15040 NE 95TH ST., #101
REDMOND, WA 98052
(425) 881-8622

MECHANICAL ENGINEER

MFIA INC CONSULTING ENGINEERS
2007 SE ASH STREET
PORTLAND, OR 97214
(503) 234-0548

ELECTRICAL ENGINEER

MFIA INC CONSULTING ENGINEERS
2007 SE ASH STREET
PORTLAND, OR 97214
(503) 234-0548



THIS PROJECT INCLUDES THE INTERIOR REMODEL OF AN EXISTING CRITICAL ACCESS HOSPITAL FACILITY THAT IS TO REMAIN OPERATIONAL AT ALL TIMES. CONTRACTOR BIDS SHALL BE BASED ON VERIFICATION OF EXISTING ON-SITE CONDITIONS. UNINTERRUPTED ESSENTIAL HEALTHCARE SERVICES DURING THE CONSTRUCTION PERIOD, ONGOING COORDINATION OF ALL RELATED TRADES FOR CURRENT CODE COMPLIANCE, PATIENT SAFETY, JURISDICTIONAL REVIEW, SYSTEM PERFORMANCE AND UNFORESEEN CLINICAL DISRUPTIONS.

INTERIOR REMODEL FOR:



211 SKYLINE DRIVE
WHITE SALMON, WASHINGTON 98612

PROJECT NUMBER: 18002c
DATE: 2/14/2018
DRAWN: CW
REVISIONS:

BASEMENT
KITCHEN
ELECTRICAL PLAN

E3.2

© 2018 BLUE ROOM ARCHITECTURE & DESIGN, P.S.