

GENERAL NOTES:

1. DEMOLISH EXISTING ELECTRICAL EQUIPMENT IN ELECTRICAL ROOM. COORDINATE WITH PGE TO REMOVE EXISTING METER. SEE DEMO PLAN.
2. DISCONNECT POWER TO ALL EXISTING RECEPTACLES. RECONNECT POWER TO WHERE SHOWN.
3. DISCONNECT POWER TO ALL EXISTING LIGHT FIXTURES. RELOCATE AND RE-CIRCUIT PER E2.1. SEE E0.2 FOR EXISTING FIXTURES.
4. PROVIDE METERING EQUIPMENT PER UTILITY REQUIREMENT.

RECORD DRAWING:
 THIS DRAWING HAS BEEN UPDATED TO REFLECT CHANGES MADE DURING CONSTRUCTION BASED UPON INFORMATION FURNISHED TO THE ENGINEER BY THE INSTALLATION CONTRACTOR. NO WARRANTY, EITHER EXPRESSED OR IMPLIED, IS GIVEN BY M.B.A. AS TO THE ACCURACY AND/OR COMPLETENESS OF THIS INFORMATION.


AS-BUILT PREPARED 1.22.2020

FOSTER SHELTER
 6144 SE FOSTER RD, PORTLAND, OREGON 97206
 CLIENT: MULTNOMAH COUNTY

MBA MERRYMAN BARNES ARCHITECTS 4713 N ALBINA AVE, SUITE 304 PORTLAND, OREGON 97217 P:503.222.3793

SHEET NOTES:

1. COORDINATE WITH LOCAL FIRE MARSHALL TO PROVIDE A KNOX BOX. VERIFY LOCATION.
2. EXISTING TELECOM DEMARK POINT. COORDINATE WITH UTILITY IF REQUIRED TO RELOCATE THE EXISTING EQUIPMENT TO MAKE ROOM FOR NEW DOOR.
3. PROVIDE A NEW LIGHTING CONTROL WITH ASTRONOMICAL TIME CLOCK, INTERMETIC; ET1115C OR EQUAL. PROVIDE CREDIT IF EXISTINGS ARE REUSABLE.



1 ELECTRICAL ROOM LAYOUT
 E3.4 SCALE: 1/2" = 1'-0"

PROJECT NO.	ISSUE DATE
17-0918	05.04.2018
REVISIONS	CHECKSHEET 5.23.2018
	OWNER CHANGES 2.26.2019

SHEET
 ELECTRICAL ROOM LAYOUT
E3.4
 PERMIT SET
 © MERRYMAN BARNES ARCHITECTS, INC.