
16,597

OREGON

BID





GENERAL NOTES:

THE INSTALLATION DATE.

MEASURED FROM FINAL GRADE.

PROVIDER, TELCO, AND CATV.

NOT BE OBSTRUCTED.

PLAN NOTES:

FINISHES OF DEVICES AND FIXTURES.

CONNECTION TO FIRE ALARM SYSTEM.

CONSTRUCTION.

A. TECHNOLOGY DRAWINGS ARE DIAGRAMMATICAL AND MAY NOT ACCURATELY REFLECT ACTUAL CONSTRUCTION CONDITIONS. THE

C. COORDINATE WITH LOCAL UTILITY PROVIDER FOR EXACT SERVICE

CONDUIT SIZES AND LOCATION TO ROUTE TO CONDUIT TO.

D. CUSTOMER TO PROVIDE ALL TRENCHING AND BACKFILLING. TRENCH TO BE 36 INCHES DEEP AND 30 INCHES WIDE,

E. CONSULT WITH UTILITY PROVIDER REPRESENTATIVE 2 WEEKS

ARCHITECTURAL DRAWINGS FOR ALL MOUNTING HEIGHTS AND

H. FOR VOICE/DATA OUTLETS PROVIDE A SINGLE GANG MUD-RING WITH A 1" CONDUIT FROM THE TOP OF THE MUD-RING TO

ACCESSIBLE CEILING SPACE. TERMINATE CONDUIT WITH END

CONNECTORS AND THREAD ON PLASTIC BUSHING FOR CABLE

PROTECTION. OUTLET SHALL BE AT THE SAME HEIGHT AS ADJACENT POWER OUTLET AND LESS THAN 18" SEPARATION. COORDINATE WITH ELECTRICAL.

ARCHITECTURAL INTERIOR ELEVATIONS TO VERIFY DEVICES WILL

J. REFER TO ENLARGED TYPICAL UNIT PLANS (IF PROVIDED) FOR TYPICAL LAYOUTS FOR ALL APARTMENT UNIT TYPES.

1. (2)-2" CONDUITS TO POWER POLE STUB 12" ABOVE GRADE.

COORDINATE ALL DEVICE LOCATIONS WITH LATEST

SMOKE, FIRE/SMOKE DAMPERS, AND ROOF TOP UNITS REQUIRING

BEFORE STARTING MAIN POWER TRENCHING FOR A PRE-CONSTRUCTION CONFERENCE. INCLUDED IN THIS CONFERENCE WILL BE EXCAVATOR, TECHNOLOGY UTILITY

F. THE TECHNOLOGY CONTRACTOR SHALL REFER TO THE

G. COORDINATE WITH MECHANICAL PLANS FOR LOCATIONS OF

TECHNOLOGY CONTRACTOR SHALL BE RESPONSIBLE FOR

COORDINATING THE INSTALLATION OF ALL TECHNOLOGY


EQUIPMENT, WITH ALL TRADES PRIOR TO AND DURING

B. TECHNOLOGY ENTRANCE LOCATION DESIGN IS BASED ON INFORMATION PROVIDED BY THE UTILITY THRU THE DESIGN PROCESS. HOWEVER IT IS UP TO THE CONTRACTOR TO VERIFY CONDITIONS AND REQUIREMENTS HAVE NOT CHANGED PRIOR TO

EMMONS - NORTH BUILDING 680 NW 18TH AVENUE, PORTLAND, OR

NORTHWEST

PROJECT NO. 17004 03/12/2021



SITE PLAN — NORTH BUILDING