

**1 PART 1 GENERAL****2 DESCRIPTION**

3 The provisions of the General Requirements, Supplementary Requirements, and Division 1 apply to the  
4 plumbing work specified in this Division.

5  
6 The requirements of this section apply to the fire suppression system.

7  
8 Provide all items, articles, materials, equipment, operations and/or methods listed, mentioned, shown and/or  
9 scheduled on the Drawings and/or in these Specifications, including all design, labor, supervision, services,  
10 permits, fees, and incidentals necessary and required to modify the sprinkler system in areas of work noted  
11 and provide a complete and operable facility with complete systems as shown, specified, and required by  
12 applicable codes. Provide all labor and material and perform such other services necessary and reasonably  
13 incidental to the design and installation of an automatic sprinkler system for all areas indicated on the  
14 Drawings.

15  
16 Alter existing systems for remodeled areas. See Drawings for remodeled areas.

**17 QUALITY ASSURANCE****18 Contractor Qualifications:**

19 Established fire protection contractor regularly engaged in the design and installation of automatic fire  
20 sprinkler systems.

21 Employ workers experienced and skilled in this trade.

22 System Designer: Qualified and certified for the design of fire protection sprinkler systems. NICET  
23 level III or IV technician or Professional Engineer experienced in the design of sprinkler systems.

24 Drawings shall be sealed by a licensed professional engineer experienced in fire protection.

25  
26  
27 Governing Agency: All work in accordance with and accepted by the following hereafter referred to  
28 Governing Agencies:

29 City of Salem Fire Marshal.

**30 Design Requirements:**

31 Comply with the latest issue of NFPA Standard 13.

32 Modify the existing wet pipe sprinkler system for the altered ceilings or room lay-outs. Design, layout  
33 and install an equivalent system to match existing protection level or new hazard level as noted  
34 utilizing code approved automatic devices designed particularly for use in this type of system.

35 Provide justification or calculation methods required by authority having jurisdiction.

36 Fire Sprinkler Coverage: Match current level of coverage and density.

37 Occupancy Hazard: Final Occupancy Hazard designation in accordance with the Governing Agency  
38 requirements.

39 Seismic Restraint: Include load calculations for seismic restraints on drawings.

40 Revisions to the Contractor's design required by the Governing Agency shall be at the Contractor's  
41 expense.

42  
43  
44 Acceptable Manufacturers: All sprinkler specialty material Grinnell/Gem, Central, Reliable, Globe, Star,  
45 Viking, Automatic Sprinkler Corp. of America with UL or FM approval for use in automatic sprinkler systems.

46 All materials and equipment suitable for 175 psi working pressure.

**47 WORK OF OTHER CONTRACTS**

48 Work under this contract shall be conducted in a manner to allow for the future installations of such equipment  
49 or items listed in other sections of this Specification.

**50 WORK OF OTHER DIVISIONS**

51 Work under this Division shall be conducted in a manner to cooperate with the installation of such equipment  
52 or items as specified in other Divisions.

53  
54  
55

- 1 Consult all Drawings and Specifications in this project and become familiar with all equipment to be installed.
- 2 Coordinate all aspects of the construction with the other trades on the job to ensure that all work and
- 3 materials required to provide a complete and operational facility are included in the bid.
- 4
- 5 Provide AutoCAD drawings and files to other trades for coordination. Prepare accurate shop drawings
- 6 showing the actual physical dimensions required for the installation. Submit prior to
- 7 purchase/fabrication/installation of any of the elements involved in the coordination.
- 8
- 9 Coordination of piping and heads is particularly critical in auditorium. Review all auditorium drawings in
- 10 preparation of design.

11  
12 **SUBMITTALS**

13 Working Drawings:

- 14 Prepare fire protection system working drawing showing locations and types of heads or outlets,
- 15 alarm valves and devices, pipe sizes and cutting lengths, test tees and valves, drain valves, and other
- 16 related items. Plans shall comply with the requirements of Chapter 8, 2013 NFPA 13, irregardless of
- 17 the edition adopted by the Governing Agencies and used for design. Plans shall be stamped and
- 18 signed by the licensed profession engineer responsible for the design.
- 19 Provide 3 sets of drawings showing sprinkler head locations and layout coordinated with architectural
- 20 ceiling details to the Architect for review prior to submitting details to the Governing Agencies.
- 21 Provide 6 sets of drawings to the Architect to be provided to Insurance Underwriter for approval.
- 22 Provide 6 sets of drawings to designated representatives of the Fire Marshal for approval.
- 23 Then provide 6 sets of approved Drawings to the Architect for final review.

24  
25 Submittals:

- 26 Sprinkler Heads: Product data for each type of head.
- 27 System control valves.
- 28 Piping materials.

29  
30 Test Reports: Submit certificates of completion of tests and inspections.

31  
32 **EXTRA STOCK**

33 Additional Heads: Provide number, type and temperature rating installed as required to meet NFPA 13

34 requirements.

35  
36 Storage Cabinet: Provide as required to receive reserve sprinkler heads and special installation tools

37 required.

38  
39 Index Label: Provide for each head indicating manufacturer, model, orifice, size or K-factor, and temperature

40 rating. Also provide inside cabinet a list of heads stored within and brief description of where installed.

41  
42 **WARRANTY**

43 Furnish, prior to application for final payment, three copies of written and signed guarantee effective a period

44 of one year from date of completion and acceptance of entire project; agree to correct, repair and/or replace

45 defective materials and/or equipment or the results of defective workmanship without additional expense to

46 the Owner. Where no response satisfactory to the Owner has occurred within three working days from the

47 written report of a warranty covered defect, the contractor shall agree to pay for the cost of repair of the

48 reported defect by a contractor of the Owner's choice.

49  
50 Where the manufacturer's guarantee exceeds one year, the longer guarantee shall govern and include the

51 Contractor's labor.

52  
53 Warranty shall cover new systems only.

54

55 **PART 2 PRODUCTS**

56 **MATERIALS AND EQUIPMENT**

57 Miscellaneous Sprinkler Specialties: Complete system including all items required by the Governing Agency.

1  
2 Sprinkler Heads: Approved heads with temperature ratings required for service indicated. All shall be quick  
3 response early suppression type and rated heads.

4 Unfinished Areas: Upright, pendant or sidewall spray type, plain bronze.

5 Finished Areas: Chrome plated recessed and sidewall heads in finished ceilings, and where piping is  
6 exposed use chrome plated upright heads.

7 At contractor's option, flexible sprinkler head drops may be used in lieu of rigid piping. Hose  
8 assembly shall be UL 2443 listed and FM 1637 approved. Devices shall approved per be IBC 1621  
9 or ASCE 7 as an alternative to seismic escutcheons. Ceiling attachment bracket shall be seismically  
10 certified. Hose assembly constructed of fully welded corrugated 304 stainless steel hose with  
11 stainless steel overbraid with threaded stainless steel pipe fittings. Device shall be listed for 175 PSI  
12 working pressure. Hose and 304 stainless steel threaded ends shall be welded per AHSI / AWS  
13 B2.1-00. No gaskets, O-rings, flares, or similar mechanical joints permitted. FlexHead Industries or  
14 equal.

15  
16 Escutcheons: Provide polished chrome escutcheons on pipe extending through finished walls and ceilings.  
17 Provide oversized escutcheon to comply with current code.

18  
19 Above Ground Water Piping: Use standard weight (schedule 40) black or galvanized steel pipe ASTM A53,  
20 A135, or A795, and cast iron screwed or mechanical joint fittings especially adapted and approved for  
21 sprinkler work. Use reducing fittings where changes in pipe size occur. Bushings are prohibited. Galvanized  
22 pipe required for dry system.

23  
24 At Contractor's option, Schedule 10 black or galvanized steel pipe ASTM A135 or ASTM A795, and  
25 mechanical joint fittings specifically approved for sprinkler use, may be substituted for the black steel pipe  
26 specified above. Pipe shall be UL listed and FM approved for 300 psi working pressure. Pipe must have a  
27 CRR of 1.00 or greater.

28  
29 Restrictions:

30 Schedule 5 pipe is not allowed.

31  
32 Valves: UL and/or FM listed for fire protection service.

33 Iron body OS&Y pattern, bronze mounted double disc, parallel seat.

34 Iron body butterfly style with EPDM liner, bronze disc with lever or indicating type gear operator.

35 Bronze body ball valve, three-piece design, with approved operator.

36 Where required by Governing Agency, provide wall or post style indicating valves.

37 Standpipe Valves: Angle or straight pattern rough brass gate valve with cap and retaining chain.

### 38 39 **PART 3 EXECUTION**

#### 40 **INSTALLATION**

41 Connect to water supply source as shown on Drawings, check adequacy, and call any deficiency to attention  
42 of Architect. Coordinate with work in Division 22 and 23.

43  
44 Install all piping in a true and even manner with lines pitched for drainage and system arranged so that it can  
45 be entirely emptied of water. Install hangers at all branch line connections to cross mains and at all other  
46 points as required in hereinbefore specified Underwriters Laboratories, Inc. and NFPA standards.

47  
48 Support all pipe work from building construction with mild steel hangers spaced not more than 12 feet on  
49 centers. Support mains independently of branches, and in no case shall branch hangers assume any portion  
50 of the weight of mains. Provide seismic restraints and flexible connections in accordance with building code  
51 requirements.

52  
53 Locate sprinkler heads in repeating, modular pattern, centered and accurately coordinated with ceiling grid as  
54 indicated. Conceal all piping unless indicated otherwise. Coordinate design with lighting and exposed HVAC  
55 duct layout in areas without ceilings.

**FIRE SUPPRESSION SPRINKLER SYSTEM**

**21 13 00-4**

- 1 Locate and install the required fire sprinkler alarm, flow, and test and drain valves where required by the
- 2 Governing Agency.
- 3
- 4 Where sprinkler lines penetrate fire rated partitions, provide fire stopping system in accordance with Section
- 5 22 05 00.
- 6
- 7 **TEST**
- 8 Test all pipes to a hydrostatic pressure of 200 psi and maintain for four hours minimum. Perform other tests
- 9 as directed by Governing Agency.
- 10
- 11 **PAINT**
- 12 Paint all exposed piping and hangers in accordance with Section 09 91 00. Do not paint heads.
- 13
- 14 **CERTIFICATE OF COMPLETION**
- 15 Obtain and deliver to Owner a certificate, in duplicate, stating that system as installed has been inspected and
- 16 accepted by authorities and/or agencies having jurisdiction, and that all regulations affecting work have been
- 17 satisfied. Submit an acceptable certificate to the Owner before final payment is requested.
- 18
- 19 Certificate: Minimum NFPA Figure 16-1 information per NFPA 13.
- 20
- 21
- 22 

END OF SECTION