



GENERAL SHEET NOTES:

1. CONTRACTOR TO VERIFY LOCATION AND SIZES OF EXISTING DUCTWORK, PIPING, EQUIPMENT, CONTROLS, ETC. PRIOR TO COMMENCING WORK. IF SHOWN LOCATION OR SIZE DIFFER FROM PLANS, LOCATE THE CORRECT SIZE ON SITE AND ADJUST CONNECTION ACCORDINGLY. PROVIDE NEW DUCT, PIPING, EQUIPMENT, CONTROLS AND ETC. IF ONE IS NOT PRESENT.
2. CONTRACTOR TO DEMOLISH PIPE, DUCTWORK, CONTROLS WIRING, ETC., INCLUDING PIPE, DUCTWORK, WIRING NOT SHOWN ON THE CONSTRUCTION DOCUMENTS. CAP ALL UNUSED DUCT, PIPE AND WIRING TO OUTSIDE OF THE AREA OF PROJECT SCOPE.
3. CONTRACTOR TO PROVIDE UL LISTED 3M FIRE STOPPING AT ALL NEW AND EXISTING PIPE AND DUCT PENETRATIONS, INCLUDING PENETRATIONS NOT SHOWN ON THE CONSTRUCTION DOCUMENTS.
4. SOME DEMO AND NEW WORK FALLS OUTSIDE OF THE OUTLINE OF THE PHASES OR PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR SETTING THE APPROPRIATE INFECTIOUS CONTROL BOUNDARIES FOR EACH CONSTRUCTION PHASE.
5. CONTRACTOR TO KEEP RECORD OF NEW SYSTEM, CONTROLS, PIPING, DUCTWORK INSTALLED AS WELL AS EXISTING TO REMAIN, AND ITEMS DISCOVERED OR ENCOUNTERED ON SITE THAT WERE NOT SHOWN ON THE PLANS. THESE INCLUDE SYSTEMS, DUCTWORK, PIPE, ETC THAT DO NOT AFFECT OR ARE NOT PART OF THE PROJECT SCOPE, BUT ARE WITHIN THE BOUNDARIES OF THE PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS THAT ACCURATELY REFLECT THE CONDITIONS WITHIN THE BOUNDARY OF THE PROJECT SCOPE AT THE END OF THE PROJECT.
6. PIPING LOCATIONS SHOWN ON THE PLAN ARE APPROXIMATE. CONTRACTOR TO VERIFY EXACT LOCATION PRIOR TO COMMENCING WORK.
7. SEE P6.00 FOR PLUMBING LEGEND, SCHEDULES AND DETAILS.
8. SEE ARCHITECTURAL INTERIOR ELEVATIONS FOR EXACT MEDICAL GAS OUTLETS AND MEDICAL VACUUM INLET LOCATIONS.


KEYED NOTES:

- (A) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO TWO NEW MASTER ALARM PANELS; LOCATE ONE (MAP-1) IN ENGINEERING OFFICE (VERIFY EXACT LOCATION WITH FACILITY MAINTENANCE MANAGER) AND THE SECOND ONE (MAP-2) AT THE NURSING STATION (SEE PLAN FOR LOCATION);
- (B) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-1;
- (C) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-2;
- (D) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-3;
- (E) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-4;
- (F) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-5;
- (G) MEDICAL GASSES TO EQUIPMENT BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.
- (H) MEDICAL GASSES TO ANESTHESIA ROOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.


FUNCTIONAL PERFORMANCE TESTING:
ALL MECHANICAL, PLUMBING AND MEDICAL GAS SYSTEMS TO BE FUNCTIONAL TESTED AS REQUIRED BY OAR 333-535-0300 (1)(I), AND ALL TESTING REPORTS BE GIVEN TO THE ENGINEER OF RECORD FOR REVIEW.



1 PARTIAL FLOOR PLAN- MEDICAL GAS
P3.11 1/4"=1'-0"



ISSUE DATE:	06.05.2015
REVISIONS:	
ADD#1	05.28.2015
SAME DAY REV.10-5-15	
ASI #7	2-25-16
CCD # 05	4-14-17
CCD # 06	5-1-17



1 PARTIAL FLOOR PLAN- MEDICAL GAS
P3.12 1/4"=1'-0"


KEYED NOTES:

- (A) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO TWO NEW MASTER ALARM PANELS; LOCATE ONE (MAP-1) IN ENGINEERING OFFICE (VERIFY EXACT LOCATION WITH FACILITY MAINTENANCE MANAGER) AND THE SECOND ONE (MAP-2) AT THE NURSING STATION (SEE PLAN FOR LOCATION);
- (B) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-1;
- (C) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-2;
- (D) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-3;
- (E) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-4;
- (F) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-5;
- (G) MEDICAL GASSES TO EQUIPMENT BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.
- (H) MEDICAL GASSES TO ANESTHESIA BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.

FUNCTIONAL PERFORMANCE TESTING:
ALL MECHANICAL, PLUMBING AND MEDICAL GAS SYSTEMS
TO BE FUNCTIONAL TESTED AS REQUIRED BY OAR
333-535-0300 (1)(I), AND ALL TESTING REPORTS BE
GIVEN TO THE ENGINEER OF RECORD FOR REVIEW.

GENERAL SHEET NOTES:

- CONTRACTOR TO VERIFY LOCATION AND SIZES OF EXISTING DUCTWORK, PIPING, EQUIPMENT, CONTROLS, ETC. PRIOR TO COMMENCING WORK. IF SHOWN LOCATION OR SIZE DIFFER FROM PLANS, LOCATE THE CORRECT SIZE ON SITE AND ADJUST CONNECTION ACCORDINGLY. PROVIDE NEW DUCT, PIPING, EQUIPMENT, CONTROLS AND ETC. IF ONE IS NOT PRESENT.
- CONTRACTOR TO DEMOLISH PIPE, DUCTWORK, CONTROLS WIRING, ETC., INCLUDING PIPE, DUCTWORK, WIRING NOT SHOWN ON THE CONSTRUCTION DOCUMENTS. CAP ALL UNUSED DUCT, PIPE AND WIRING TO OUTSIDE OF THE AREA OF PROJECT SCOPE.
- CONTRACTOR TO PROVIDE UL LISTED 3M FIRE STOPPING AT ALL NEW AND EXISTING PIPE AND DUCT PENETRATIONS, INCLUDING PENETRATIONS NOT SHOWN ON THE CONSTRUCTION DOCUMENTS.
- SOME DEMO AND NEW WORK FALLS OUTSIDE OF THE OUTLINE OF THE PHASES OR PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR SETTING THE APPROPRIATE INFECTIOUS CONTROL BOUNDARIES FOR EACH CONSTRUCTION PHASE.
- CONTRACTOR TO KEEP RECORD OF NEW SYSTEM, CONTROLS, PIPING, DUCTWORK INSTALLED AS WELL AS EXISTING TO REMAIN, AND ITEMS DISCOVERED OR ENCOUNTERED ON SITE THAT WERE NOT SHOWN ON THE PLANS. THESE INCLUDE SYSTEMS, DUCTWORK, PIPE, ETC THAT DO NOT AFFECT OR ARE NOT PART OF THE PROJECT SCOPE, BUT ARE WITHIN THE BOUNDARIES OF THE PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS THAT ACCURATELY REFLECT THE CONDITIONS WITHIN THE BOUNDARY OF THE PROJECT SCOPE AT THE END OF THE PROJECT.
- PIPING LOCATIONS SHOWN ON THE PLAN ARE APPROXIMATE. CONTRACTOR TO VERIFY EXACT LOCATION PRIOR TO COMMENCING WORK.
- SEE P6.00 FOR PLUMBING LEGEND, SCHEDULES AND DETAILS.
- SEE ARCHITECTURAL INTERIOR ELEVATIONS FOR EXACT MEDICAL GAS OUTLETS AND MEDICAL VACUUM INLET LOCATIONS.



KEYED NOTES:

- (A) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO TWO NEW MASTER ALARM PANELS; LOCATE ONE (MAP-1) IN ENGINEERING OFFICE (VERIFY EXACT LOCATION WITH FACILITY MAINTENANCE MANAGER) AND THE SECOND ONE (MAP-2) AT THE NURSING STATION (SEE PLAN FOR LOCATION);
- (B) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-1;
- (C) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-2;
- (D) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-3;
- (E) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-4;
- (F) MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-5;
- (G) MEDICAL GASSES TO EQUIPMENT BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.
- (H) MEDICAL GASSES TO ANESTHESIA BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.

FUNCTIONAL PERFORMANCE TESTING:
ALL MECHANICAL, PLUMBING AND MEDICAL GAS SYSTEMS TO BE FUNCTIONAL TESTED AS REQUIRED BY OAR 333-535-0300 (1)(I), AND ALL TESTING REPORTS BE GIVEN TO THE ENGINEER OF RECORD FOR REVIEW.

1 PARTIAL FLOOR PLAN- MEDICAL GAS
P3.13 1/4"=1'-0"

GENERAL SHEET NOTES:

- CONTRACTOR TO VERIFY LOCATION AND SIZES OF EXISTING DUCTWORK, PIPING, EQUIPMENT, CONTROLS, ETC. PRIOR TO COMMENCING WORK. IF SHOWN LOCATION OR SIZE DIFFER FROM PLANS, LOCATE THE CORRECT SIZE ON SITE AND ADJUST CONNECTION ACCORDINGLY. PROVIDE NEW DUCT, PIPING, EQUIPMENT, CONTROLS AND ETC. IF ONE IS NOT PRESENT.
- CONTRACTOR TO DEMOLISH PIPE, DUCTWORK, CONTROLS WIRING, ETC., INCLUDING PIPE, DUCTWORK, WIRING NOT SHOWN ON THE CONSTRUCTION DOCUMENTS. CAP ALL UNUSED DUCT, PIPE AND WIRING TO OUTSIDE OF THE AREA OF PROJECT SCOPE.
- CONTRACTOR TO PROVIDE UL LISTED 3M FIRE STOPPING AT ALL NEW AND EXISTING PIPE AND DUCT PENETRATIONS, INCLUDING PENETRATIONS NOT SHOWN ON THE CONSTRUCTION DOCUMENTS.
- SOME DEMO AND NEW WORK FALLS OUTSIDE OF THE OUTLINE OF THE PHASES OR PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR SETTING THE APPROPRIATE INFECTIOUS CONTROL BOUNDARIES FOR EACH CONSTRUCTION PHASE.
- CONTRACTOR TO KEEP RECORD OF NEW SYSTEM, CONTROLS, PIPING, DUCTWORK INSTALLED AS WELL AS EXISTING TO REMAIN, AND ITEMS DISCOVERED OR ENCOUNTERED ON SITE THAT WERE NOT SHOWN ON THE PLANS. THESE INCLUDE SYSTEMS, DUCTWORK, PIPE, ETC. THAT DO NOT AFFECT OR ARE NOT PART OF THE PROJECT SCOPE, BUT ARE WITHIN THE BOUNDARIES OF THE PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS THAT ACCURATELY REFLECT THE CONDITIONS WITHIN THE BOUNDARY OF THE PROJECT SCOPE AT THE END OF THE PROJECT.
- PIPING LOCATIONS SHOWN ON THE PLAN ARE APPROXIMATE. CONTRACTOR TO VERIFY EXACT LOCATION PRIOR TO COMMENCING WORK.
- SEE P6.00 FOR PLUMBING LEGEND, SCHEDULES AND DETAILS.
- SEE ARCHITECTURAL INTERIOR ELEVATIONS FOR EXACT MEDICAL GAS OUTLETS AND MEDICAL VACUUM INLET LOCATIONS.

GENERAL SHEET NOTES:


1. CONTRACTOR TO VERIFY LOCATION AND SIZES OF EXISTING DUCTWORK, PIPING, EQUIPMENT, CONTROLS, ETC. PRIOR TO COMMENCING WORK. IF SHOWN LOCATION OR SIZE DIFFER FROM PLANS, LOCATE THE CORRECT SIZE ON SITE AND ADJUST CONNECTION ACCORDINGLY. PROVIDE NEW DUCT, PIPING, EQUIPMENT, CONTROLS AND ETC. IF ONE IS NOT PRESENT.
2. CONTRACTOR TO DEMOLISH PIPE, DUCTWORK, CONTROLS WIRING, ETC., INCLUDING PIPE, DUCTWORK, WIRING NOT SHOWN ON THE CONSTRUCTION DOCUMENTS. CAP ALL UNUSED DUCT, PIPE AND WIRING TO OUTSIDE OF THE AREA OF PROJECT SCOPE.
3. CONTRACTOR TO PROVIDE UL LISTED 3M FIRE STOPPING AT ALL NEW AND EXISTING PIPE AND DUCT PENETRATIONS, INCLUDING PENETRATIONS NOT SHOWN ON THE CONSTRUCTION DOCUMENTS.
4. SOME DEMO AND NEW WORK FALLS OUTSIDE OF THE OUTLINE OF THE PHASES OR PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR SETTING THE APPROPRIATE INFECTIOUS CONTROL BOUNDARIES FOR EACH CONSTRUCTION PHASE.
5. CONTRACTOR TO KEEP RECORD OF NEW SYSTEM, CONTROLS, PIPING, DUCTWORK INSTALLED AS WELL AS EXISTING TO REMAIN, AND ITEMS DISCOVERED OR ENCOUNTERED ON SITE THAT WERE NOT SHOWN ON THE PLANS. THESE INCLUDE SYSTEMS, DUCTWORK, PIPE, ETC THAT DO NOT AFFECT OR ARE NOT PART OF THE PROJECT SCOPE, BUT ARE WITHIN THE BOUNDARIES OF THE PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS THAT ACCURATELY REFLECT THE CONDITIONS WITHIN THE BOUNDARY OF THE PROJECT SCOPE AT THE END OF THE PROJECT.
6. PIPING LOCATIONS SHOWN ON THE PLAN ARE APPROXIMATE. CONTRACTOR TO VERIFY EXACT LOCATION PRIOR TO COMMENCING WORK.
7. SEE P6.00 FOR PLUMBING LEGEND, SCHEDULES AND DETAILS.
8. SEE ARCHITECTURAL INTERIOR ELEVATIONS FOR EXACT MEDICAL GAS OUTLETS AND MEDICAL VACUUM INLET LOCATIONS.





KEYED NOTES:

- (A) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO TWO NEW MASTER ALARM PANELS; LOCATE ONE (MAP-1) IN ENGINEERING OFFICE (VERIFY EXACT LOCATION WITH FACILITY MAINTENANCE MANAGER) AND THE SECOND ONE (MAP-2) AT THE NURSING STATION (SEE PLAN FOR LOCATION);
- (B) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-1;
- (C) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-2;
- (D) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-3;
- (E) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-4;
- (F) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-5;
- (G) — MEDICAL GASSES TO EQUIPMENT BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.
- (H) — MEDICAL GASSES TO ANESTHESIAN BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.

FUNCTIONAL PERFORMANCE TESTING:
ALL MECHANICAL, PLUMBING AND MEDICAL GAS SYSTEMS
TO BE FUNCTIONAL TESTED AS REQUIRED BY OAR
333-535-0300 (1)(I), AND ALL TESTING REPORTS BE



1 PARTIAL FLOOR PLAN-- MEDICAL GAS
P3.14 1/4"=1'-0"




ISSUE DATE: 06.05.2015

REVISIONS:

- ADD#1 05.28.2015
SAME DAY REV. 10-5-15
ASI #7 2-25-16

GENERAL SHEET NOTES:

1. CONTRACTOR TO VERIFY LOCATION AND SIZES OF EXISTING DUCTWORK, PIPING, EQUIPMENT, CONTROLS, ETC. PRIOR TO COMMENCING WORK. IF SHOWN LOCATION OR SIZE DIFFER FROM PLANS, LOCATE THE CORRECT SIZE ON SITE AND ADJUST CONNECTION ACCORDINGLY. PROVIDE NEW DUCT, PIPING, EQUIPMENT, CONTROLS AND ETC. IF ONE IS NOT PRESENT.
2. CONTRACTOR TO DEMOLISH PIPE, DUCTWORK, CONTROLS WIRING, ETC., INCLUDING PIPE, DUCTWORK, WIRING NOT SHOWN ON THE CONSTRUCTION DOCUMENTS. CAP ALL UNUSED DUCT, PIPE AND WIRING TO OUTSIDE OF THE AREA OF PROJECT SCOPE.
3. CONTRACTOR TO PROVIDE UL LISTED 3M FIRE STOPPING AT ALL NEW AND EXISTING PIPE AND DUCT PENETRATIONS, INCLUDING PENETRATIONS NOT SHOWN ON THE CONSTRUCTION DOCUMENTS.
4. SOME DEMO AND NEW WORK FALLS OUTSIDE OF THE OUTLINE OF THE PHASES OR PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR SETTING THE APPROPRIATE INFECTIOUS CONTROL BOUNDARIES FOR EACH CONSTRUCTION PHASE.
5. CONTRACTOR TO KEEP RECORD OF NEW SYSTEM, CONTROLS, PIPING, DUCTWORK INSTALLED, AS WELL AS EXISTING TO REMAIN, AND ITEMS DISCOVERED OR ENCOUNTERED ON SITE THAT WERE NOT SHOWN ON THE PLANS. THESE INCLUDE SYSTEMS, DUCTWORK, PIPE, ETC THAT DO NOT AFFECT OR ARE NOT PART OF THE PROJECT SCOPE, BUT ARE WITHIN THE BOUNDARIES OF THE PROJECT SCOPE. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS-BUILT DRAWINGS THAT ACCURATELY REFLECT THE CONDITIONS WITHIN THE BOUNDARY OF THE PROJECT SCOPE AT THE END OF THE PROJECT.
6. PIPING LOCATIONS SHOWN ON THE PLAN ARE APPROXIMATE. CONTRACTOR TO VERIFY EXACT LOCATION PRIOR TO COMMENCING WORK.
7. SEE P6.00 FOR PLUMBING LEGEND, SCHEDULES AND DETAILS.





1 PENTHOUSE FLOOR PLAN- MEDICAL GAS
P3.15
1/4"=1'-0"

KEYED NOTES:

- (A) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO TWO NEW MASTER ALARM PANELS; LOCATE ONE (MAP-1) IN ENGINEERING OFFICE (VERIFY EXACT LOCATION WITH FACILITY MAINTENANCE MANAGER) AND THE SECOND ONE (MAP-2) AT THE NURSING STATION (SEE PLAN FOR LOCATION);
- (B) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-1;
- (C) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-2;
- (D) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-3;
- (E) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-4;
- (F) — MEDICAL GAS PRESSURE SENSOR/TRANSDUCER WIRED TO AP-5;
- (G) — MEDICAL GASSES TO EQUIPMENT BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.
- (H) — MEDICAL GASSES TO ANESTHESIA BOOM. SEE VENDOR GAS DETAILS FOR INSTALLATION REQUIREMENTS.

FUNCTIONAL PERFORMANCE TESTING:
ALL MECHANICAL, PLUMBING AND MEDICAL GAS SYSTEMS
TO BE FUNCTIONAL TESTED AS REQUIRED BY OAR
333-535-0300 (1)(0), AND ALL TESTING REPORTS BE



ISSUE DATE: 06.05.2015

REVISIONS:
△ SAME DAY REV. 10-5-15
△ ASI #7 2-25-16