


(E) 24X24 OSA LOUVER

**1** MECH DEMO PLAN  
 M1.0 SCALE: 3/16" = 1'-0"

- KEY NOTES:**
- (A) — DEMO (E) SUPPLY AIR DUCTWORK FROM ALL WATER SOURCE HEAT PUMPS.
  - (B) — (E) OA DUCTWORK TO REMAIN.
  - (C) — DEMO (E) RETURN/SUPPLY GRILL.
  - (D) — ALL (E) EXHAUST DUCTWORK, FAN, GRILLES, LOUVER AND F/S DAMPER TO REMAIN.
  - (E) — (E) EQUIPMENT TO REMAIN.

No.	Date	No.	Issue
05		18012	No
04			
03			
02			
01			

Sheet Name:  
**MECH - DEMO  
 PLAN**



**1 MECH FLOOR PLAN**  
 M2.0 SCALE: 3/16" = 1'-0"

- KEY NOTES:**
- (A) — SUPPLY AIR DUCTWORK TO CONNECT TO (E) EQUIPMENT.
  - (B) — CONNECT OA DUCTWORK TO (E) EQUIPMENT. INSTALL NEW BALANCING DAMPER.
  - (C) — COORDINATE DUCTWORK AND DIFFUSER LOCATION WITH NEW LIGHTING.
  - (D) — INSTALL NEW THERMOSTATS AT LOCATIONS INDICATED.
  - (E) — 6" RA FROM CLOSET TO RETURN AIR PLENUM OF (E) WATER SOURCE HEAT PUMP.
  - (F) — (E) EXHAUST FAN AND SYSTEM TO REMAIN AS-IS — SEE ELECT DRAWINGS FOR NEW TIME CLOCK.
  - (G) — (E) OA DUCTWORK.
  - (H) — EXISTING WATER SOURCE HEAT PUMP, RETURN AIR PLENUM, FILTERS AND OSA CONNECTION TO BE RE-USED AS-IS FOR NEW SPACE LAYOUT. COORDINATE CEILING AND ACCESS LOCATIONS WITH EXISTING EQUIPMENT HUNG FROM UNI-STRUT.


05			
04			
03			
02	18012	No	
01	Date	Issue	
No			

Sheet Name:  
**MECH FLOOR  
 PLAN**

### MECHANICAL LEGEND

	SUPPLY AIR DIFFUSER	AFF	ABOVE FINISH FLOOR
	RETURN AIR GRILLE	AHU	AIR HANDLING UNIT
	EXHAUST AIR GRILLE	B.D.	BOTTOM OF DUCT
	PERFORATED RETURN AIR PANEL	BHP	BRAKE HORSEPOWER
	DIRECTIONAL AIR FLOW	BTU	BRITISH THERMAL UNITS
	MANUAL VOLUME DAMPER	CFM	CUBIC FEET PER MINUTE
	SUPPLY OR OUTSIDE AIR DUCT UP & DOWN	CONN.	CONNECTION
	RETURN AIR DUCT UP & DOWN	CONT.	CONTINUATION
	EXHAUST AIR DUCT UP & DOWN	CW	DOMESTIC COLD WATER
	SUPPLY OR OUTSIDE AIR DUCT UP & DOWN	DB	DRY BULB
	RETURN AIR DUCT UP & DOWN	DIA.	DIAMETER
	EXHAUST AIR DUCT UP & DOWN	DIST.	DISTRIBUTION
	SUPPLY OR OUTSIDE AIR DUCT UP & DOWN	EA	EXHAUST AIR
	RETURN AIR DUCT UP & DOWN	EDB	ENTERING DRY BULB TEMPERATURE
	EXHAUST AIR DUCT UP & DOWN	EWB	ENTERING WET BULB TEMPERATURE
	SUPPLY OR OUTSIDE AIR DUCT UP & DOWN	EWT	ENTERING WATER TEMPERATURE
	RETURN AIR DUCT UP & DOWN	FF	FINISH FLOOR
	EXHAUST AIR DUCT UP & DOWN	FIXT.	FIXTURE
	VAV TERMINAL UNIT	FPM	FEET PER MINUTE
	WT TERMINAL UNIT	FPS	FEET PER SECOND
	EXISTING	FT.	FEET / FOOT
	CONNECT TO EXISTING	GA.	GAUGE
	THERMOSTAT OR TEMP. SENSOR	GPM	GALLONS PER MINUTE
	NOTE	H	HEIGHT
	EQUIPMENT DESIGNATOR	HP	HORSEPOWER
	BALL VALVE	I.D.	INSIDE DIAMETER
	GATE VALVE	IN.	INCHES
	CHECK VALVE	L	LENGTH
	BALANCING VALVE	LBS.	POUNDS
	THERMOMETER	LDB	LEAVING DRY BULB
	DIRECTION OF FLOW	LWB	LEAVING WET BULB
	PUMP	LWT	LEAVING WATER TEMPERATURE
	STRAINER	MAX.	MAXIMUM
	PRESSURE GAUGE	MBH	THOUSANDS OF BTUs PER HOUR
	PETE'S PLUG	MIN.	MINIMUM
	DOUBLE CHECK ASSEMBLY	NC	NORMALLY CLOSED
	PRESSURE REDUCING VALVE	N.C.	NORMALLY CLOSED
	UNION	N.I.M.	NOT IN MECHANICAL
	2-WAY CONTROL VALVE	NO.	NUMBER
	3-WAY CONTROL VALVE	N.O.	NORMALLY OPEN
	CAP	O.A.	OUTSIDE AIR
	SMOKE DETECTOR	P	PERSON
	MOTORIZED DAMPER	PSI	POUNDS PER SQUARE INCH
	SEISMIC BRACING	P/T	PRESSURE / TEMPERATURE
		R.A.	RETURN AIR
		RECT.	RECTANGULAR
		REQ'D	REQUIRED
		S.A.	SUPPLY AIR
		S.P.	STATIC PRESSURE
		SQ.	SQUARE
		TEMP.	TEMPERATURE
		TYP.	TYPICAL
		VAV	VARIABLE AIR VOLUME
		W	WIDTH
		WB	WET BULB
		WPD	WATER PRESSURE DROP
		ϕ	DIAMETER
			(E) EXISTING
			(D) DEMOLISH
			NEW WORK
			HWS (HWS) HEATING WATER SUPPLY
			HWR (HWR) HEATING WATER RETURN
			FIRE DAMPER
			FIRE / SMOKE DAMPER
			SMOKE DAMPER
			SEISMIC BRACING
			LATERAL BRACING
			LONGITUDINAL BRACING
			LONGITUDINAL & LATERAL BRACING

### AIR DISTRIBUTION DETAILS



### VENTILATION AIR SCHEDULE - FC-1

ROOM NUMBER AND NAME	AREA (SQ. FT.)	OCCUPANT LOAD (#/1000 SQ. FT.)	NUMBER OF OCCUPANTS	OUTSIDE AIR REQUIREMENT (CFM/P)	OUTSIDE AIR REQUIREMENT (CFM/SQ. FT.)	OUTSIDE AIR REQUIRED (CFM)	ZONE OSA (CFM)	SUPPLY AIR (CFM)	PRIMARY OSA FRACTION	RETURN AIR (CFM)	EXHAUST AIR (CFM)	Zone Ventilation Efficiency	Corrected OSA CFM	AIR SYSTEMS	
	<b>Az</b>		<b>Pz</b>	<b>Rp</b>	<b>Ra</b>	<b>Vbz</b>	<b>Ez</b>	<b>Voz</b>	<b>Zp</b>			<b>Evz</b>			
OFFICE	127	5	1	5	0.06	13	0.8	16	300	0.05	0	0	1.04	16.30	FC-1
OFFICE	246	5	2	5	0.06	25	0.8	31	500	0.06	0	0	1.03	31.99	FC-1
LOBBY	220	15	7	7.5	0.12	79	0.8	99	800	0.12	0	0	0.97	101.93	FC-1
<b>TOTAL</b>	<b>593</b>		<b>10</b>			<b>116</b>		<b>145</b>	<b>1600</b>		<b>0</b>	<b>0</b>	<b>0.97</b>	<b>150</b>	
<b>CORRECTED TOTAL OUTDOOR AIR FLOW RATE</b>										<b>150</b>	<b>CFM</b>	<b>Corrected OSA Fraction</b>	<b>Zs =</b>	<b>0.09</b>	

### VENTILATION AIR SCHEDULE - FC-2

ROOM NUMBER AND NAME	AREA (SQ. FT.)	OCCUPANT LOAD (#/1000 SQ. FT.)	NUMBER OF OCCUPANTS	OUTSIDE AIR REQUIREMENT (CFM/P)	OUTSIDE AIR REQUIREMENT (CFM/SQ. FT.)	OUTSIDE AIR REQUIRED (CFM)	ZONE OSA (CFM)	SUPPLY AIR (CFM)	PRIMARY OSA FRACTION	RETURN AIR (CFM)	EXHAUST AIR (CFM)	Zone Ventilation Efficiency	Corrected OSA CFM	AIR SYSTEMS	
	<b>Az</b>		<b>Pz</b>	<b>Rp</b>	<b>Ra</b>	<b>Vbz</b>	<b>Ez</b>	<b>Voz</b>	<b>Zp</b>			<b>Evz</b>			
EXHIBIT GALLERY	768	15	25	7.5	0.06	234	0.8	292	1600	0.18	0	0	1.00	291.98	FC-2
<b>TOTAL</b>	<b>768</b>		<b>25</b>			<b>234</b>		<b>292</b>	<b>1600</b>		<b>0</b>	<b>0</b>	<b>1.00</b>	<b>292</b>	
<b>CORRECTED TOTAL OUTDOOR AIR FLOW RATE</b>										<b>292</b>	<b>CFM</b>	<b>Corrected OSA Fraction</b>	<b>Zs =</b>	<b>0.18</b>	

### VENTILATION AIR SCHEDULE - FC-3

ROOM NUMBER AND NAME	AREA (SQ. FT.)	OCCUPANT LOAD (#/1000 SQ. FT.)	NUMBER OF OCCUPANTS	OUTSIDE AIR REQUIREMENT (CFM/P)	OUTSIDE AIR REQUIREMENT (CFM/SQ. FT.)	OUTSIDE AIR REQUIRED (CFM)	ZONE OSA (CFM)	SUPPLY AIR (CFM)	PRIMARY OSA FRACTION	RETURN AIR (CFM)	EXHAUST AIR (CFM)	Zone Ventilation Efficiency	Corrected OSA CFM	AIR SYSTEMS	
	<b>Az</b>		<b>Pz</b>	<b>Rp</b>	<b>Ra</b>	<b>Vbz</b>	<b>Ez</b>	<b>Voz</b>	<b>Zp</b>			<b>Evz</b>			
EXHIBIT GALLERY	1446	20	36	7.5	0.06	357	0.8	446	1600	0.28	0	0	1.00	445.95	FC-3
<b>TOTAL</b>	<b>1446</b>		<b>36</b>			<b>357</b>		<b>446</b>	<b>1600</b>		<b>0</b>	<b>0</b>	<b>1.00</b>	<b>446</b>	
<b>CORRECTED TOTAL OUTDOOR AIR FLOW RATE</b>										<b>446</b>	<b>CFM</b>	<b>Corrected OSA Fraction</b>	<b>Zs =</b>	<b>0.28</b>	

### VENTILATION AIR SCHEDULE - FC-4

ROOM NUMBER AND NAME	AREA (SQ. FT.)	OCCUPANT LOAD (#/1000 SQ. FT.)	NUMBER OF OCCUPANTS	OUTSIDE AIR REQUIREMENT (CFM/P)	OUTSIDE AIR REQUIREMENT (CFM/SQ. FT.)	OUTSIDE AIR REQUIRED (CFM)	ZONE OSA (CFM)	SUPPLY AIR (CFM)	PRIMARY OSA FRACTION	RETURN AIR (CFM)	EXHAUST AIR (CFM)	Zone Ventilation Efficiency	Corrected OSA CFM	AIR SYSTEMS	
	<b>Az</b>		<b>Pz</b>	<b>Rp</b>	<b>Ra</b>	<b>Vbz</b>	<b>Ez</b>	<b>Voz</b>	<b>Zp</b>			<b>Evz</b>			
KITCHEN / RESEARCH AREA	295	70	5	7.5	0.18	91	0.8	113	600	0.19	0	0	0.93	122.37	FC-4
COLLECTIONS WORKROOM	426	40	4	7.5	0.06	56	0.8	69	1000	0.07	0	0	1.04	75.05	FC-4
<b>TOTAL</b>	<b>721</b>		<b>9</b>			<b>146</b>		<b>183</b>	<b>1600</b>		<b>0</b>	<b>0</b>	<b>0.93</b>	<b>197</b>	
<b>CORRECTED TOTAL OUTDOOR AIR FLOW RATE</b>										<b>197</b>	<b>CFM</b>	<b>Corrected OSA Fraction</b>	<b>Zs =</b>	<b>0.12</b>	

CLIMATE  
architecture +  
landscape, LLC

M  
E  
T  
A  
INC.  
Consulting Engineers  
2007 S.E. Ash St.  
Portland, OR 97214  
PHN: (503) 234-0548  
FAX: (503) 234-0677  
WWW.MET-ENG.COM  
CONTACT: MARK DENYER

General Contractor  
**T.B.D.**  
Address:

Project  
**OREGON NIKKEI LEGACY CENTER**  
Address:  
411 NW FLANDERS ST  
PORTLAND, OR 97201

Architect  
**climate ARCHITECTURE + LANDSCAPE, LLC**  
Address:  
205A NE MILK JB BLVD, SUITE 205A  
PORTLAND, OREGON 97212  
PH: 646-408-4971

Professional Seal:  
**11-26-19**  
REGISTERED PROFESSIONAL  
MARK R. DENYER  
JULY 11 2009  
OREGON  
**[EXPIRES: 31DEC19]**

05  
04  
03  
02  
01  
No. Date No. Issue

Sheet Name:  
**MECHANICAL SCHEDULES**

Climate 2019  
Date: 11/26/2019  
Sheet No.: **M6.0**  
Scale: 1/8" = 1'-0"  
Climate Job No.: 18012  
CAD File Name: