

EAST ELEVATION

SCALE: 1/8" = 1'-0"

SOUTH

WEST

NORTH

SCALE: 1/8" = 1'-0"

DOOR SCHEDULE

NO.	SIZE	TYPE	FRAME	LVR.	MTL.	FINISH	HDWR.	REMARK
1	7'-0" x 3'-0"	A	WOOD	—	WOOD	P-103	1	
2	0	—	—	—	—	—	1	
3	0	—	—	—	—	—	1	
4	0	—	—	—	—	—	1	
5	0	—	—	—	—	—	2	
6	0	—	—	—	—	—	2	
7	6'-11 1/2" x 3'-0"	B	—	—	—	P-102	3	
8	0	—	—	—	—	—	3	
9	0	—	—	—	—	—	3	
10	0	—	—	—	—	—	3	
11	0	—	—	—	—	—	2	
12	0	—	—	—	—	—	2	
13	0	—	—	—	—	—	3	
14	0	—	—	—	—	—	3	
15	0	—	—	—	—	—	3	

FINISH SCHEDULE

RM.	NO.	FLOOR	WALLS	CEILING	TRIM	CAB.	REMARKS
CLASS	101	VAT.	R.B.	P-100	—	—	CEDAR PANELING ABOVE 7'-2 1/2" (3) WALLS
CLASS	102	VAT.	R.B.	—	—	—	C.T. VNSCT. UP 6'-0" ALL WALLS
GIRLS	103	C.T.	C.T.	—	—	—	C.T. VNSCT. UP 6'-0" ALL WALLS
WORK	104	VAT.	R.B.	—	—	—	C.T. VNSCT. UP 6'-0" ALL WALLS
BOYS	105	C.T.	C.T.	—	—	—	C.T. VNSCT. UP 6'-0" ALL WALLS
HALL	106	VAT.	R.B.	—	—	—	CEDAR PANELING ABOVE 7'-2 1/2" (3) WALLS
CLASS	107	—	—	—	—	—	LAM. P. BACKSPLASH & S.S.
CLASS	108	—	—	—	—	—	24" x 24" WILCOR CEIL. A.P. IN JAN.
JAN.	109	—	—	—	—	—	

DOOR TYPES

(A) SOLID CORE WOOD 1/4" TEMP. GL.

EXTERIOR FINISH

SIDING: 1C/PRE STAIN
TRIM: P-103
METAL: P-104
DECKING: P-103
CONC.: 2C/SILICONE SEALER

NOTES: ALL EXT. CLASS GRAYLITE
- TEMP. & LOW WINDS
- PROVIDE WATER PROOF GYP. BD.
@ WEST WALL (107), EAST WALL (108)
SOUTH 107 & 108 & ALL WALLS REST ROOMS.

FLOOR PLAN

SCALE: 1/8" = 1'-0"

SQUARE FOOTAGES

BUILDING FOOTAGE - 5160 #
COVERED AREA (BASIC BID) - 940 #
COVERED AREA (ALT. #1) - 2700 #

SCHEDULE OF DRAWINGS

PG. NO.	DESCRIPTION
1	SITE, FOUNDATION, ROOF FRAMING PLAN
2	FLOOR PLAN, ELEVATIONS, SCHEDULES
3	DETAILS
4	INTERIOR ELEVATIONS & DETAILS
M-1	MECHANICAL SITE PLAN
M-2	FOUNDATION PLAN
M-3	FLOOR PLAN
E-1	LIGHTING, POWER, & SIGNALS
E-2	ELECTRICAL SITE PLAN, RISERS & SYMBOLS

ARCHITECTS
VANE STRABLE
ASSOCIATES
AND ASSOCIATES
P.C.

ADDITION TO
BELLVIEW ELEMENTARY SCHOOL
ASHLAND, OREGON SCHOOL DISTRICT NO. 5

FLOOR PLAN
ELEVATIONS
SCHEDULES

DATE: APRIL 17, 1967
JOB NO. 66158
DRAWN BY DS
REV.

2
OF 4
TOTAL SHEETS 9