2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

SECTION 23 74 00 - CENTRAL STATION HVAC UNITS

PART 1 - GENERAL

SECTION INCLUDES

Indoor Air Handling Units.

Roof Mounted Package Heating and Cooling Units.

REFERENCES

AFBMA 9 - Load Ratings and Fatigue Life for Ball Bearings.

- AMCA 99 Standards Handbook.
- AMCA 210 Laboratory Methods of Testing Fans for Rating Purposes.
- AMCA 300 Test Code for Sound Rating Air Moving Devices.
- AMCA 500 Test Methods for Louver, Dampers, and Shutters.
- AHRI 410 Forced-Circulation Air-Cooling and Air-Heating Coils.
- AHRI 430 Central-Station Air-Handling Units.
- AHRI 435 Application of Central-Station Air-Handling Units.
- ASTMB117 Standard Practice for Operating Salt Spray Apparatus.
- NEMA MG1 Motors and Generators.
- NFPA 70 National Electrical Code.
- SMACNA HVAC Duct Construction Standards Metal and Flexible.
- UL 723 Test for Surface Burning Characteristics of Building Materials.
- UL 900 Test Performance of Air Filter Units.
- UL 1995 Standard for Heating and Cooling Equipment.
- UL 94 Test for Flammability of Plastic Materials for Parts in Devices and Appliances.
- IBC 2000, 2003 International Building Code.
- NFPA 90A Standard for the Installation of Air Conditioning and Ventilating Systems.
- NFPA 5000 Building Construction and Safety Code.
- ASHRAE 90.1 Energy Code.

2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

AHRI Standard 1060 - Rating Air-to-Air Heat Exchangers for Energy Recovery Ventilation Equipment.

GSA 2003 Facilities Standard - 5.9 HVAC Systems and Components.

SUBMITTALS

Shop Drawings: Indicate assembly, unit dimensions, weight loading, required clearances, construction details, field connection details, and electrical characteristics and connection requirements. Computer generated fan curves for each air handling unit shall be submitted with specific design operating point noted. A computer generated psychometric chart shall be submitted for each cooling coil with design points and final operating point clearly noted. Sound data for discharge, radiated and return positions shall be submitted by octave band for each unit. Calculations for required baserail heights to satisfy condensate trapping requirements of cooling coil shall be included.

Product Data:

Provide literature that indicates dimensions, weights, capacities, ratings, fan performance, finishes of materials, electrical characteristics, and connection requirements.

Provide data of filter media, filter performance data, filter assembly, and filter frames.

Provide manufacturer's installation instructions.

QUALIFICATIONS

For Rooftop Package Units: A factory representative shall meet with Control Contractor to review sequence of operations and assist Control Contractor in generating a sequence of operation. Instances #'s from the factory controller shall be part of the sequence. See Section 23 09 23 for more information and requirements.

SAFETY AGENCY LISTED & CERTIFICATION

Air handler furnished with double width, double inlet (DWDI) fans and/or plenum fans where applicable, shall be certified in accordance with the central station air handling units certification program, which is based on AHRI Standard 430. (NOTE: Above does not apply to fan array).

Air handling unit water heating & cooling coils shall be certified in accordance with the forced circulation air cooling and air heating coils certification program, which is based on AHRI Standard 410.

DELIVERY, STORAGE, AND HANDLING

Deliver, store, protect and handle products to site.

Accept products on site on factory-furnished shipping skids. Inspect for damage.

Store in clean dry place and protect from construction traffic. Handle carefully to avoid damage to components, enclosures, and finish.

2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

PART 2 - PRODUCTS

CENTRAL STATION AIR HANDLERS

Unit Construction

Configuration: Fabricate as detailed on drawings.

Performance: Conform to AHRI 430. See schedules on prints. (NOTE: above does not apply to fan array).

Acoustics: Sound power levels (dB) for the unit shall not exceed the specified levels shown on the unit schedule. The manufacturer shall provide the necessary sound treatment to meet these levels if required.

Fabricate unit with heavy gauge channel posts and panels secured with mechanical fasteners. All panels, access doors, and ship sections shall be sealed with permanently applied bulb-type gasket. Shipped loose gasketing is not allowed.

Panels and access doors shall be constructed as a 2-inch nominal thick; thermal broke double wall assembly, injected with foam insulation with an R-value of not less than R-13 or equal fiberglass.

The inner liner shall be constructed of G90 galvanized steel.

The outer panel shall be constructed of G90 galvanized steel.

The floor plate shall be constructed as specified for the inner liner.

Unit will be furnished with solid inner liners at coil panels. Perforated at all others.

Panel deflection shall not exceed L/240 ratio at 125% of design static pressure, maximum 5 inches of positive or 6 inches of negative static pressure. Deflection shall be measured at the panel midpoint.

The casing leakage rate shall not exceed .5 cfm per square foot of cabinet area at 5 inches of positive static pressure or 6 inches of negative static pressure.

Module to module field assembly shall be accomplished with an overlapping, full perimeter internal splice joint that is sealed with bulb type gasketing on both mating modules to minimize on-site labor and meet indoor air quality standards.

Access doors shall be flush mounted to cabinetry, with minimum of two six inch long stainless steel piano-type hinges, latch and full size handle assembly. Access doors shall swing outward for unit sections under negative pressure. Access doors on positive pressure sections, shall have a secondary latch to relieve pressure and prevent injury upon access.

A formed G60 galvanized steel base rail shall be provided by the unit manufacturer for structural rigidity and condensate trapping.

Fan Assemblies

2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

Where housed fans are noted, acceptable fan assembly shall be a double width, double inlet, class II, belt-drive type housed forward curved fan dynamically balanced as an assembly, as shown in schedule. Maximum fan RPM shall be below first critical fan speed. Fan assemblies shall be dynamically balanced by the manufacturer on all three planes and at all bearing supports. Copper lubrication lines shall be provided and extend from the bearings and attached with grease fittings to the fan base assembly near access door. If not supplied at the factory, Contractor shall mount copper lube lines in the field. Fan and motor shall be mounted internally on a steel base. Provide access to motor, drive, and bearings through hinged access door.

Acceptable fan assembly shall be a single width, single inlet, class II, direct-drive type plenum fan dynamically balanced as an assembly, as shown in schedule. Maximum fan RPM shall be below first critical fan speed. Fan assemblies shall be dynamically balanced by the manufacturer on all three planes. Provide access to motor and fan assembly through hinged access door. Selections shall not result in fan speeds greater than 70 Hz at design conditions.

Fan and motor shall be mounted internally on a steel base. Factory mount motor on slide base that can be slid out the side of the unit if removal is required. Provide access to motor, drive, and bearings through hinged access door. Fan and motor assembly shall be mounted on minimum 1.5" deflection spring vibration type isolators inside cabinetry. Seismic snubbers shall be provided.

Bearings, Shafts, and Drives

Bearings: Basic load rating computed in accordance with AFBMA - ANSI Standards. The bearings shall be designed for service with an L-50 life of 200,000 hours and shall be a heavy duty pillow block, self-aligning, grease-lubricated ball or spherical roller bearing type.

Shafts shall be solid, hot rolled steel, ground and polished, keyed to shaft, and protectively coated with lubricating oil. Hollow shafts are not acceptable.

V-Belt drives shall be cast iron or steel sheaves, dynamically balanced, bored to fit shafts and keyed. Fixed sheaves, matched belts, and drive rated based on motor horsepower. Minimum of 2 belts shall be provided on all fans with 10 HP motors and above. Standard drive service factor minimum shall be 1.1 S.F. for 1/4 HP – 7.5 HP, 1.3 S.F. for 10 HP and larger, calculated based on fan brake horsepower.

Electrical

Fan motors shall be manufacturer provided and installed, Open Drip Proof, premium efficiency (meets or exceeds EPAct requirements), 1750 RPM, single speed VFD compatible. Complete electrical characteristics for each fan motor shall be as shown in schedule. Provide with shaft grounding on all motors 5 HP and larger with VFD, Aegis Inc., SGR Series or equal.

The air handler(s) shall be ETL listed.

Unit shall be factory wired from single disconnect to individual fan motors.

See Section 23 05 00 for VFD requirements.

Disconnect requirements:

Motor circuit protectors or UL 489 circuit breakers. All disconnects shall include a lock-out mechanism when in the off position.

The Motor Circuit protector shall be a UL listed 508 current limiting manual motor starter with magnetic trip elements only. The breaker shall carry a UL 508F rating (up to 100A frame size) which provides for coordinated short circuit rating for use with the motor contactor and provides a minimum interrupting rating of 30,000 AIC for the combination starter.

2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

Disconnect shall be UL 98 suitable for service entrance protection.

UL 489 breaker shall include thermal and magnetic trip mechanisms.

Provide all conduit and conductors. Install per NEC.

All electrical connection components shall be field provided and mounted as shown on project schedule.

Provide smoke detector for field installation. Include with the option to allow the installation of a monitoring module from the Fire Alarm System.

Heating and Cooling Water Coils

Certification: Acceptable water coils shall be certified in accordance with AHRI Standard 410 and bear the AHRI label. Coils exceeding the scope of the manufacturer's certification and/or the range of AHRI's standard rating conditions will be considered provided the manufacturer is a current member of the AHRI Forced Circulation Air-Cooling and Air-Heating Coils certification programs and that the coils have been rated in accordance with AHRI Standard 410. Manufacturer must be ISO 9002 certified.

Provide Drain pan for cooling coil. Construct drain pans from stainless steel with cross break and double sloping pitch to drain connection. Provide drain pans under cooling coil section. Drain connection centerline shall be a minimum of 3" above the base rail to aid in proper condensate trapping. Drain connections that protrude from the base rail are not acceptable. There must be a full 2" thickness of insulation under drain pan.

Provide access to coil(s) for service and cleaning. Enclose coil headers and return bends fully within unit casing. Unit shall be provided with coil connections that extend a minimum of 5" beyond unit casing for ease of installation. Drain and vent connections shall be provided exterior to unit casing. Coil connections must be factory sealed with grommets on interior and exterior panel liners to minimize air leakage and condensation inside panel assembly. If not factory packaged, Contractor must supply all coil connection grommets and sleeves. Coils shall be removable through side and/or top panels of unit without the need to remove and disassemble the entire section from the unit.

Headers shall consist of seamless copper tubing to assure compatibility with primary surface. Headers to have intruded tube holes to provide maximum brazing surface for tube to header joint, strength, and inherent flexibility. Header diameter should vary with fluid flow requirements.

Fins shall have a minimum thickness of 0.0075 inch aluminum plate construction. Fins shall have full drawn collars to provide a continuous surface cover over the entire tube for maximum heat transfer. Tubes shall be mechanically expanded into the fins to provide a continuous primary to secondary compression bond over the entire finned length for maximum heat transfer rates. Bare copper tubes shall not be visible between fins.

Coil tubes shall be 5/8 inch OD seamless copper, 0.020 inch nominal tube wall thickness, expanded into fins, brazed at joints.

Coil connections shall be carbon steel, threaded connection. Vent and drain fittings shall be furnished on the connections, exterior to the air handler. Vent connections provided at the highest point to assure proper venting. Drain connections shall be provided at the lowest point to insure complete drainage and prevent freeze-up.

Filters

Furnish angled or flat filter section as shown on drawings with 2-inch MERV 8 filter.

2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

Provide filter frames for the installation of roll media per Section 23 40 00.

Plenum / Access Sections

Plenum section shall be provided and properly sized for inlet and/or discharge air flow (between 600 and 1500 feet per minute). The plenum shall provide single or multiple openings as shown on drawings and project schedule.

Access section shall be provided for access between hot water coil and cooling coil section, between future cooling section and fan inlet for servicing of fan and backdraft dampers of fan array., and where shown on drawings for servicing components. All access doors on the discharge side of supply air stream shall be inward opening against pressure.

Economizer Sections

Dampers shall be provided with opposed blade low leak airfoil damper blades. Dampers shall be hollow core galvanized steel airfoil blades, fully gasketed and have continuous vinyl seals between damper blades in a galvanized steel frame. Dampers shall have stainless steel jamb seals along end of dampers. Linkage and ABS plastic end caps shall be provided when return and outside air dampers sized for full airflow. Return and outside air dampers of different sizes or very large dampers and exhaust dampers must be driven separately. Damper Leakage: Leakage rate shall be less than two tenths of one percent leakage at 2 inches static pressure differential or 4 CFM/sq. ft at 1"wc whichever is more restrictive. Leakage rate tested in accordance with AMCA Standard 500. Openings shall be configured as shown on drawings.

Approved manufactures: Trane, Carrier, Daikin, or Johnson Controls only.

PART 3 - EXECUTION

INSTALLATION

Install in accordance with manufacturer's Installation & Maintenance instructions.

See Commissioning specification for additional requirements.

Manufacturer's Field Service: Engage a factory authorized service representative to inspect field assembled components and equipment installation, to include electrical and piping connections. Report results to A/E in writing. Inspection must include a complete startup checklist to include (as a minimum) the following: Completed Start-Up Checklists as found in manufacturer's IOM.

Engage a factory authorized service representative to perform startup service. Install clean filters. Measure and record electrical values for voltage and amperage. Refer to Division 23 "Testing, Adjusting and Balancing" and comply with provisions therein.

Engage a factory authorized service representative to train Owner's maintenance personnel to adjust, operate and maintain the entire unit. Refer to Division 01 Section Closeout Procedures and Demonstration and Training.

At air handlers include materials and labor to wire factory provided field installed smoke detectors to shut down VFD's at fan system when smoke is detected.

2022 RENOVATION & REPAIR PROJECTS FOR THE SALEM KEIZER SCHOOL DISTRICT

ENVIRONMENTAL REQUIREMENTS

Do not operate units for any purpose, temporary or permanent, until ductwork is clean, filters are in place, bearings lubricated, and fan has been test run under observation.

EXTRA MATERIALS

Provide one extra set(s) filters for each unit as shown on project schedule.

Filters: Specified filters or approved temporary construction filters shall be installed in supply units prior to start-up or used for drying and/or temporary heat. See specifications related to ensuring ducts remain clean during construction for more information.

PIPING

Refer to applicable sections for piping, ductwork, insulation, painting, etc.

CONTROLS

Wiring: All wiring shall be in accordance with the National Electrical Code and local electrical codes.

END OF SECTION 23 74 00